

Westinghouse Overview and AP1000[®] Plant Projects Update



October 2013

AP1000 is a trademark or registered trademark of Westinghouse Electric Company LLC, its affiliates and/or its subsidiaries in the United States of America and may be registered in other countries throughout the world. All rights reserved. Unauthorized use is strictly prohibited. Other names may be trademarks of their respective owners.



Westinghouse Electric Company

- Incorporated in 1886 by George Westinghouse
- Responsible for some of the world's most important achievements:
 - AC technology
 - 1st commercial radio broadcast
 - USS Nautilus
 - 1st camera on the moon
 - **Commercial nuclear power**



Westinghouse Electric Company Business Structure

Engineering, Equipment and Major Projects

Focused on ensuring new and operating plant success by providing technically superior engineering, hardware and services that enhance plant safety, ensure plant reliability, extend plant life and improve plant performance

Nuclear Power Plants

Specializing in the development and delivery of new nuclear power plant projects



Nuclear Fuel

A single-source fuel provider for PWR, BWR, VVER and AGR reactors worldwide

Automation and Field Services

A global field services and instrumentation and control solutions provider, focused on delivering industry-leading operations solutions and better outage services worldwide



Westinghouse Locations



60+ sites worldwide!

AP1000 Plant Global Project Delivery

- Eight **AP1000** units under construction worldwide
 - Four units in China
 - Four units in the United States



V.C. SUMMER

VOGTLE

HAIYANG

SANMEN





China AP1000 Plant Projects

Haiyang 1&2
Shandong Province

Sanmen 1&2
Zhejiang Province



First Build of a New Standard Advanced Passive Generation III+ Plant




Passive safety features

The concept of standardized plants for China supports the country's fleet approach, aligns with the technology transfer principles and assists supply chain.




AP1000 – Simplified PWR Design

Comparison of Important Nuclear Island Buildings AP1000™




Darker areas shown are Seismic I category buildings





- | | |
|-------------------------------|------------------------------------|
| 1. Shield / Containment | 7. Refueling Water Storage Tank |
| 2. Auxiliary Building | 8. Demineralizer / Potable Water P |
| 3. Fuel Area | 9. Condensate Storage Tank |
| 4. Diesel Generators | 10. Radwaste Building |
| 5. Service Water Pumphouse | 11. Annex Building |
| 6. Emergency Fuel Oil Storage | |

~45% less Seismic Category 1 building volume



AP1000 – Station Black Out



China AP1000 Plant Progress: Sanmen

Unit 1 First Concrete – March 2009



Unit 2 SG/Refueling Canal Module – December 2010



Unit 1 Reactor Vessel – August 2011




Unit 1 CVTH Set – January 2013



China AP1000 Plant Progress: Haiyang

Unit 1 First Concrete – September 2009



Unit 2 Auxiliary Building – December 2010



Unit 1 Reactor Vessel – January 2012



Unit 1 CVTH Set – March 2013



Progress of China Projects: Summary

- Major equipment delivered and installed at Sanmen Unit 1 and Haiyang Unit 1 includes:
 - Reactor Vessel
 - Steam Generators
 - Reactor Vessel Internals
 - Polar Crane
 - Integrated Head Package
- Containment Vessel Top Head (CVTH) set at Sanmen Unit 1 in January 2013 and Haiyang Unit 1 in March 2013
- Digital I&C turnover to Startup staff in progress
- Potential Sanmen operators have completed simulator training; Haiyang operators started simulator training in July
- Technology transfer well advanced



Photo © Sanmen Nuclear Power Company, Ltd. All rights reserved.



Photo © Shandong Nuclear Power Company, Ltd. All rights reserved.


Sanmen Site Progress: Time Lapse View



2009 to 2013



U.S. AP1000 Plant Projects



Vogtle 3&4
Waynesboro, Georgia

V.C. Summer 2&3
Jenkinsville, South Carolina



AP1000 U.S. Design & Licensing Milestones

- U.S. Nuclear Regulatory Commission (NRC) approved amended design in December 2011 in 5-0 vote
- Combined construction and operating licenses (COLs) issued by U.S. NRC in February 2012 for Vogtle 3&4 site and March 2012 for V.C. Summer 2&3 site



U.S. AP1000 Plant Progress: Vogtle Site

- First nuclear concrete pour for Vogtle Unit 3 completed March 2013
- Unit 3 Containment Vessel Bottom Head (CVBH) set in Nuclear Island June 2013
- Seam welding of Unit 3 Containment Vessel lower and middle rings in progress
- Assembly of Unit 3 Condensers ongoing
- Units 3&4 Cooling Tower erection, permanent buildings and River Water Intake piping placement work ongoing
- Component and module fabrication proceeding



Photos © 2013 Georgia Power Company. All rights reserved.

U.S. AP1000 Plant Progress: Vogtle Site

- Welding of first Shield Building panel commenced January 2013
- Unit 3 Reactor Vessel delivered April 2013
- First phase of backfill completed for Unit 3 Cooling Tower, Hot Water Intake and Circulating Water System piping to pumphouse
- Unit 3&4 Inspections, Tests, Analyses and Acceptance Criteria (ITAAC) continue to be submitted to NRC for review
- Unit 4 CVBH assembly near completion
- Unit 3 Auxiliary Building concrete wall placements ongoing



Photos © 2013 Georgia Power Company. All rights reserved.



U.S. AP1000 Plant Progress: V.C. Summer Site

- First nuclear concrete pour for V.C. Summer Unit 2 completed March 2013
- Unit 2 Containment Vessel Bottom Head (CVBH) set in Nuclear Island May 2013
- Unit 2 Reactor Vessel delivered June 2013
- First Westinghouse-procured equipment installed in Unit 2 Turbine Building
- Unit 2 CA20 Module (Auxiliary Building) assembly continues at site



Photos © 2013 South Carolina Electric & Gas. All rights reserved.



U.S. AP1000 Plant Progress: V.C. Summer Site

- First concrete pours for Unit 2 Auxiliary Building walls and CVBH completed August 2013
- CH80 structural frame module set in Unit 2 Turbine Building September 2013
- Unit 2 Condenser B lower shell installed in Turbine Building
- Shield Building panel fabrication in progress
- Unit 3 basemat rebar and embedded piping installation in progress



Photos © 2013 South Carolina Electric & Gas. All rights reserved.



Future AP1000 Projects

- US – Duke recently canceled due to NRC delays on issuing COLs.
- China – multiple units being planned for construction; eight additional to start this year.
- India – a preliminary commercial agreement was just signed with NPCIL for early engineering and licensing work.
- United Kingdom – currently certifying AP1000 design.
- Czech Republic – currently bidding on two AP1000 units at the Temelin site. Bid recently received top ranking.
- Middle East – just signed a collaboration agreement with Exelon and Toshiba for Saudi Arabia projects.



Thank you! Questions?

